

SITE PREPARATION COMMITMENT VIDEO

The customer must complete the following prior to Nationwide Lifts arrival for installation:

In most cases, the controller will be mounted on the top of the unit. If your jurisdiction requires the controller to be mounted elsewhere, then leave space for it on a wall near the elevator. The controller is approx. 20”w x 20”h x 8”d.

Install a 120V, single phase, 15 amp power to a fused disconnect with lockout arm. This disconnect switch must be 2-pole. The disconnect must be mounted near the controller’s location.

Install a 120V, 15amp disconnect for the elevator lighting supply. This fused disconnect with lockout arm should be near the other disconnect.

Provide telephone jack near the electrical disconnects. This can be the common house line.

Finished floors must be installed at all landing levels **BEFORE** the installation can start.

Smooth, level surface for installing the elevator, with load bearing capacity to meet impact load shown in drawings.

Hole in floor, or modified balcony rail as directed by drawings.

Overhead distance matching drawings. Overhead is the distance from upper floor level to the underside of the finished ceiling.

Where necessary, acquire applicable permits.

- Site preparation that must be modified / repaired by Nationwide Lifts will be charged according to Time and Materials. The hourly rate will be \$150 /hr.
- If the Nationwide Lifts employees cannot perform the work due to poor site preparation, and must leave the site, the customer will be charged for travel time and travel expenses. Travel rate will be \$100 /hr.
- If the site is not prepared and the installation must be rescheduled, the new date will be subject to availability.

Acceptance of Site Preparation Terms: The above terms and conditions are satisfactory and are hereby accepted. The site will be prepared as outlined above.

Signature: _____

Date of Acceptance: _____